

This is only the scope of work for the project. For more information, please contact Procurement at Purchasing@stpgov.org.

The Parish requires a Contractor to provide all labor and materials to provide and to install one (1) 3' x 3' traffic rated catch basin and cast iron grate, 16 linear feet of 11" x 18" RCPA culvert and one (1) sewer tie in. The Contractor shall also provide and install 13 cubic yards of borrow, compacted and graded to drain to the box and install sod to all disturbed areas. The project is located on the south east side of the intersection of Burvant St. and Oak St.

Specifications for the catch basin are as follows:

The catch basin is to either be cast in place or constructed out of concrete modular blocks. The lid shall be 8" thick, include an 18" x 18" cast iron grate and is to be set lower than adjacent grade to allow water to drain. The catch basin dimensions are 3' x 3' wide and will accommodate two (2) 11" x 18" RCP storm drain pipes. The work shall include all excavation, back fill and compaction of soil around the box. All of the work shall be performed in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Section 706. The Contractor is responsible for dressing any ruts or damage to the yard occurring as a result of construction at no direct pay. All debris is to be removed at no direct pay. The measurements are approximate and are to be verified by Contractor.

All work shall include all necessary signage, barricades and flagmen per LA DOTD Standard Specifications for Roads and Bridges, Section 713 and mobilization per Section 727.

The Contractor will have THIRTY (30) days to complete the project from the date stated in the Notice to Proceed issued by the Parish.