

**This is only the scope of work for the project. For more information, please contact Procurement at [purchasing@stpgov.org](mailto:purchasing@stpgov.org).**

The Contractor shall provide all materials and labor necessary to remove and replace 83 sy of concrete road panels including 12" x 6" mountable curbs, remove 30' of 15" CMP and replace with 32 ' of 11" x 18" RCPA culvert. The Contractor shall also install 6" wide curb cuts and concrete scuppers to allow water to drain and install sod over ends of pipe and all disturbed areas.

Specifications for the panels and culverts are as follows:

The concrete road panels are to be 8" thick with 4000 psi concrete, contain 12" x 6" x O/1 (0.25) welded wire mesh and are to be doweled into the adjoining panels with 5/8" dowel pins at 24" centers to existing road panels. The curbs are to be 12" x 6" with 4000 psi concrete and shall have a 6" wide curb cut and concrete scupper installed to allow drainage. The Contractor shall provide re-bar hoops installed in the panel to attach the curb to. The Contractor shall completely remove damaged panel and level and patch base material, as required, and compact to 95% standard proctor. The base material shall be A-4 Select material. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 602 and Section 707. The panels to be replaced will be identified by inspector after project has been awarded. The Contractor shall replace and seal joints in kind, i.e., construction joints or expansion joints. All debris is to be removed at no direct pay.

The culverts are to be 11" x 18" RCPA and shall be bedded in 12" of sand installed in 8" lifts up to the haunches of the pipe. The joints shall be wrapped in geo-textile fabric. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 701. All debris shall be removed at no direct pay.

The Contractor is to verify all dimensions and lengths.

The work shall include all necessary signage, barricades and flagmen per LA DOTD Standard Specifications for Roads and Bridges, Section 713 and mobilization of equipment per Section 727.

The Contractor will have thirty (30) days to complete the project from the date stated in the Notice to Proceed issued by the Parish.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.