

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stp.gov to ensure receipt of a full bid package, to be listed as a plan holder and to ensure any addenda to the bid package are received."

This is a Capital Improvement Project. The work specified in this project will require the Contractor to remove and replace existing concrete sidewalk. New sidewalk shall be 4' wide x 26' long by 4" thick constructed of 3000 PSI class M concrete with fiber mesh. Work shall include removing all tree roots under sidewalk, leveling and repairing base with A-4 select material as directed by the inspector and dressing shoulders at conclusion of work. All work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Section 706, 2016 edition. The Contractor shall provide all saw cuts necessary to remove the existing sidewalk and seal all control joints in kind. All debris shall be removed at no direct pay.

The time for completion of this project is 30 days from notice to proceed issued by the Parish.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.