

**"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stp.gov.org](mailto:purchasing@stp.gov) to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."**

Contractor shall provide all supervision, labor, materials, tools, supplies, permits and equipment necessary to improve the turn radius at Carmel Drive, intersection of Carmel and Albert Street, (R04E147), and Goldflower Lane (R04E0146), intersection of Goldflower and Albert Street Mandeville, LA (S38-T8-R11) as follows:

- Construct concrete mountable curbs, remove and install (2) concrete headwall culvert end treatments as detailed in the specifications along Carmel Dr., Mandeville, Louisiana 70448 (R04E147; S38-T8-R11); and
- Construct concrete mountable curbs, remove and replace 8" concrete road panels as detailed in the specifications along Goldflower Ln, Mandeville, Louisiana 70448 (R04E0146; S38-T8-R11).

All work shall be in accordance with LA DOTD Standard Specification's for Roads and Bridges, Section 707, 2016 edition.

All signage and barricades shall be provided, and all debris shall be removed at no direct pay.