

**This is just the Scope of Work. Please email the Procurement Department at [purchasing@stpgov.org](mailto:purchasing@stpgov.org) for more information.**

### **Scope of work/Services**

The Contractor must perform the following:

Syndey Ct. Covington, LA

**8" Concrete Road Panel:** Provide all labor and materials necessary to remove and replace concrete road panels. The panels are to 8" thick and constructed of 4000 psi concrete, contain 12" x 6" x O/1 (0.25) welded wire mesh and are to be doweled into adjoining panels with 5/8" bars 24" on center. All work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Section 602. The panels to be replaced will be identified by the inspector after project has been awarded. Panel work shall include required testing of concrete per ACO 301 providing three (3) cylinders for every 100 cubic yards of concrete placed to test for compressive strength. Cylinder breaks shall be one (1) at seven (7) days and two (2) at 28 days. Contractor shall also test for slump, air content and mixture temperature for every 50 cubic yards placed. Slump shall be 4". All testing will be at no direct pay. Contractor shall replace joints in kind and install joint sealer above all concrete joints. Work shall include all necessary saw cuts to adjoining panels to allow removal of panels to be replaced. All debris is to be removed and disposed of at no direct pay. 400 cy total for Sydney Ct.

Courtney Dr. Covington, LA

**8" Concrete Road Panel:** Provide all labor and materials necessary to remove and replace Concrete Road Panels. Panels are to 8" thick and constructed of 4000 psi concrete, contain 12" x 6" x O/1 (0.25) welded wire mesh and be doweled into adjoining panels with 5/8" bars 24" on center. All work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Section 602. Panels to be replaced have been identified by the inspector after project is awarded. Panel work shall include required testing of concrete per ACO 301 providing three (3) cylinders for every 100 cubic yards of concrete placed to test for compressive strength. Cylinder breaks shall be one (1) at seven (7) days and two (2) at 28 days. Contractor shall also test for slump, air content and mixture temperature for every 50 cubic yards placed. Slump shall be 4". All testing will be at no direct pay. Contractor shall replace joints in kind and install joint sealer above all concrete joints. Concrete quantity also includes concrete splash pads installed over end of pipes. Work shall include all necessary saw cuts to adjoining panels to allow removal of panels to be replaced. All debris is to be removed and disposed of at no direct pay.

**Contractor shall keep one lane of traffic open at all times.**

**Concrete Headwall:** All labor and materials necessary to construct and install four (4) concrete head walls. All head walls are to be 3'6" tall by 6'. 315 cy total for Courtney Dr.

The time period for completion of the project is **thirty (30) Calendar Days** from Notice to Proceed issued by the Parish.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work,

**This is just the Scope of Work. Please email the Procurement Department at [purchasing@stpgov.org](mailto:purchasing@stpgov.org) for more information.**

materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded