

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Contractor improve drainage between 145 Golden Meadow Drive and 144 Golden Meadow Drive (R03L148), Covington, Louisiana 70433 (S14-T7-R11).

Work shall include the repair of the existing catch basins between 145 Golden Meadow Drive and 144 Golden Meadow Drive by power washing, repairing and re-skimming five (5) catch basins and (1) safety end. Dayton Superior Re-Crete 20 Minute Grout or an approved equal shall be used for the work. All sink holes and points along the boxes shall be filled with dirt.

One (1) pipe joint located at 145 Golden Meadow Drive shall be shall cleaned and re-sealed with Dayton Superior Re-Crete 20 Minute Grout or an approved equal. Sink holes shall be filled with dirt.

All debris shall be removed at no direct pay. All signage and barricades shall be provided. All disturbed areas shall have sod supplied and installed.

The time period to complete the work shall be thirty (30) calendar days from issuance of the Notice to Proceed by the Parish.

All supervision, labor, materials, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.