

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stp.gov to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Scope of work/Services

Contractor shall provide all labor, materials, tools, and equipment to line the existing 23" x 36" RCPA culvert with cured in place pipe(CIPP). Work shall start at the catch basin located at 125 Kelly Dr. and ending at the outfall end of the culvert at the drainage canal. Contractor shall remove and replace one (1) concrete road panel in order to allow room for CIPP equipment to access catch basin and culvert. Further details of the work and responsibilities of the Contractor are provided in the project specification.

All traffic control devices, signs, barricades shall be provided by Contractor and all work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 602, 2016 edition. All debris shall be removed at no direct pay.

Time period of completion of the work is thirty 30 days from Notice to Proceed issued by the Parish.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.