"This is only the scope of work for the project. For more information, interested parties should contact Procurement at <u>purchasing@stpgov.org</u> to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

## Scope of Work/Services:

Contractor must provide all labor, materials, tools, and equipment to excavate and remove (2) damaged sections of 48" CMP culvert, install new sections of 48" CMP culvert, and (4) marmac couplers. Work shall require to clean, repair, and reseal (2) existing catch basins, backfill sink hole areas and install sod to all disturbed areas @ 1329 Lafitte St (R04D050; S39-T8-R11) Mandeville, Louisiana in accordance with specifications.

Contractor shall provide all signage and barricades and all debris shall be removed at no direct pay.

Contractor will be required to complete the work within thirty (30) days from Notice to Proceed issued by the Parish.