

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full bid package, to be listed as a plan holder and to ensure any addenda to the bid package are received."

The Contractor must provide all labor and materials to remove and replace 84'2" of sidewalk. New sidewalk is to be 4' wide by 4" thick and constructed of 3000 psi class M concrete. Work shall include removing all roots below sidewalk, leveling and repairing base with A-4 select material as directed by the inspector and dressing around walk after forms have been removed. All work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Section. 706, 2016 Edition. The contractor shall provide all necessary saw cuts to remove existing concrete and seal all joints in kind. All debris shall be removed at no direct pay.

Addresses and length of sidewalk to be replaced are as follows:

813 N. Pearl St. 31'6", south side of house

819 N. Pearl St. 16'2", north side of driveway

804 Lake Vermillion 10', broken concrete removed by DPW.

711 South Black Lake Ct. 26'6"

The Contractor shall verify all dimensions.

The time period for completion of the project is thirty (30) calendar days from Notice to Proceed issued by the Parish.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.