

This is only the scope of work for the project. For more information, please contact Procurement at purchasing@stpgov.org.

The Contractor shall supply all labor and materials necessary to provide and install two (2) CB-08 catch basins and grates and 55 linear feet of 8" schedule 80 PVC drain pipe including all necessary 45 degree bends and couplers. Work shall also include two (2) 8" cores into existing catch basins. Contractor shall power wash, repair and seal two (2) existing catch basins with Dayton Superior Re-crete 20 Minute Grout or approved equal. Proposed alternates to the grout shall be submitted to procurement no less than 7 days prior to quote opening and include manufacturer's specifications, literature and website. Contractor shall remove and replace one (1) driveway, formed to drain into existing catch basin and install sod in all disturbed areas. All debris shall be removed at no direct pay.

Locations and specifications for the drives are as follows:

Concrete drive is to be 6" thick with 4000 psi concrete and is located at 139 Lindsey Lane (Slidell, Louisiana). Drive shall also be doweled into the adjoining concrete with 5/8" dowel pins at 24" centers to existing road panels and include all necessary saw cuts to remove without damaging adjoining panels. Drive dimensions are 12'6" x 13'5" x 21'6". All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 706. The Contractor shall replace and seal joints in kind, ie, construction joints or expansion joints. All debris is to be removed at no direct pay. Contractor is to verify all dimensions and lengths.

Work shall include all necessary signage, barricades and flagmen per LA DOTD Standard Specifications for Roads and Bridges, Section 713 and mobilization of equipment per Section 727.