This is only the scope of work for the project. For more information, please contact Procurement at <u>purchasing@stpgov.org</u>.

The Contractor shall provide all labor and materials necessary to improve existing radius with 8" asphalt paving. The work shall also include all required excavation and grading. The Contractor shall saw cut along the edge of the existing asphalt to provide a straight, verticle edge to pave against. All debris is to be removed at no direct pay. The Contractor is to verify all dimensions.

Specifications for the asphalt are as follows:

The asphalt is to be installed in two (2) or more lifts at the south west side of intersection to widen the existing asphalt radius to the dimensions shown on the drawings. The Contractor shall saw cut along the existing asphalt to provide a smooth, straight edge to pave along. The asphalt is to be LA DOTD Type 3, 8" thick. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 501. All debris is to be removed at no direct pay.

All work shall include all necessary signage, barricades and flagmen per LA DOTD Standard Specifications for Roads and Bridges, Section 713 and mobilization of equipment per Section 727.