

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stp.gov.org](mailto:purchasing@stp.gov) to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Scope of Work

Contractor shall provide all labor, materials, tools, equipment and permits required to remove and replace 70 square yards of existing concrete road panels at 302 Rock Place (R04D134), Mandeville, LA 70448 (S40-T8-R11). Panels are to be 0.67' thick, have 0.5' x 1' 0/1 wire mesh and be constructed of 4000 psi class B concrete. All necessary saw cuts to remove panels, install 3/4" dowels on 2' centers and all required expansion and control joint shall be provided. All joints are to be sealed. All base material deemed unsuitable by the inspector shall be removed and replaced with granular material, leveled and compacted to 95% of the standard proctor. Existing panels to be removed are marked in orange paint. All work shall be done in accordance with LA DOTD Standard Plans and Specifications for Roads and Bridges, Section 602 2016 Edition.

21 linear foot of 0.5' x 0.5' barrier curb shall be removed and replaced. Curbs are to be constructed of 4000 psi class B concrete and built in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 707 2016 edition. Curbs shall have joints tooled into them when they cross panel control and expansion joints. Shoulder shall be repaired and graded to drain.

All traffic control devices shall be provided and follow the LA DOTD TCI and MUTCD details. All debris shall be removed at no direct pay.

The time period to complete the work shall be thirty (30) calendar days from issuance of the NTP by the Parish.