"This is only the scope of work for the project. For more information, interested parties should contact Procurement at <a href="mailto:purchasing@stpgov.org">purchasing@stpgov.org</a> to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

## Scope of work/Services

Contractor shall perform the following work to repair drainage between 205 Turning Leaf Lane and 209 Turning Leaf Lane (R01J081), Madisonville, LA 70447 (S21-T07-R10).

Contractor shall remove and dispose of existing timber bulkhead, concrete at bottom of ditch and regrade both ditch slopes. Contractor shall relocate the existing sewer clean out from bottom of ditch and move to slope.

Contractor shall supply all material and labor necessary to install cast-in-place concrete revetment. Revetment is to be constructed of 3000 psi class M concrete, 4" thick with fiber mesh. Concrete Revetment shall be done in accordance with LA DOTD Standard Specifications for roads and Bridges, Section 706, 2016 Edition.

Contractor shall construct two (2) concrete headwalls. Headwalls are to be 6' wide by 3.166' and 6' wide by 3.83' and constructed of 3000 PSI Class M concrete, 6" thick with fiber mesh. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 805, 2016 Edition.

Contractor shall supply and install sod to all disturbed areas. All Work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 714, 2016 Edition.

Contractor shall provide traffic control devices, signs and barricades and follow the LA DOTD TTC and MUTCD details and all debris shall be removed at no direct pay.

The time period to complete the work shall be thirty (30) calendar days from issuance of the NTP by the Parish.

All supervision, labor, materials, tools, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.