

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Scope of Work

Contractor shall provide all supervision, labor, equipment, tools, permits and materials to improve drainage near the intersection of Brewster Road (R01K001) and the entrance to Heritage Oaks Subdivision in Madisonville, LA (S16-T07-R10).

Work shall include approximately seventeen (17) linear feet of asphalt saw cutting 8" in depth and the saw cutting of a 24" A-2000 culvert to install the catch basins. Catch basin dimensions are approximately 4.5' x 3.5' with an invert of 5' from TOC on the first (1st) catch basin and 3' from TOC on the second (2nd) catch basin.

Work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Section 702, 2016 Edition. Contractor shall supply traffic control devices per the LA DOTD TCC and MUTCD standard details. All debris shall be removed at no direct pay.

The time period to complete the work shall be thirty (30) calendar days from the issuance of the Notice to Proceed by the Parish.