

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stp.gov to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Scope of work/Services

The work specified in this project will require the Contractor to supply all labor, equipment and materials to perform the following work:

All chain link fences are 9 gauge thick with bottom rails, middle & top corner braces, truss rods and tension wire at top with one strand of 30" 2 maze razor wire to match existing on the facility. All pipe is schedule 40.

This includes a lift or crane to put materials in position on site locations.

Section A: Install 100' length (50'x50'), 12' high chain link razor wire fence. Install one (1) 4' walk gate. 3" line posts and qty five (5) 4" terminal posts, core drill all holes in existing concrete.

Section B: Install 220' length (70'x150"), 12' high chain link razor wire fence. Install one (1) 4' walk gate. 3" line posts and qty five (5) 4" terminal posts, core drill all holes in existing concrete.

Tear down and haul off 57' of existing 6' high chain link fence. Cut posts off as close to cement walkway as possible and fill with concrete flush.

Install an aluminum walkway canopy (6' wide x 57' long = 342 sq. ft.) with gutters, 4"x4" aluminum posts anchored to slab. Match as close as possible to existing walkway canopies on the facility.

Install 228 sq. ft. (4' wide x 57' long x 4" thick) concrete walkway. Put dowel rods and wire in slab.

Contractor must submit list of all on-site personnel to the Parish within ten (10) days after quotes are due. The list shall include each person's full legal name, date of birth, driver's license number, race and sex. St. Tammany Parish Sheriff's Office (STPSO) shall perform background checks on all personnel. Only personnel with backgrounds cleared by the STPSO may access the job site.

Location:

St. Tammany Parish Jail

1200 Champagne Street

Covington, LA 70433

A Quote Guarantee **is not** required for this project.

The Contractor shall have ninety (90) days to complete the work upon Notice to Proceed issued by the Parish.

All supervision, labor, materials, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.