

**"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stpgov.org](mailto:purchasing@stpgov.org) to ensure receipt of a full bid package, to be listed as a plan holder and to ensure any addenda to the bid package are received."**

The Contractor must complete all work specified will be done @ 168 Lake D'Estes Dr. The work is to include removal of catch basin and 155 linear feet of 15" CMP culvert and replace with 4'x4' (3) catch basins with 6" lid and 2'x2' cast iron grates and 175 linear feet of 15" A-2000 culvert, including all required backfill and compaction. Backfill and compaction area will be at old pipe under drive with 30 cubic yards of granular fill for 70 linear feet. Remove and replace entire drive. Drive is to be constructed of 130 square yards of 4000 psi concrete, 6" thick and built per LA DOTD Standard Specifications for Roads and Bridges, Section 706.

Contractor is for responsible for removal and replacement of 16 linear feet of 6' tall wooden fencing, removal of three (3) trees, two pines and one hardwood, removing roots and backfill area as well.

Contractor will provide, install and compact 40 cubic yards of borrow at end of pipe @ pond. Contractor is to provide and install sod at all disturbed areas. Removal of all debris is to be done at no direct pay. The Contractor is responsible to verify all quantities.

The Contractor will have 30 days to complete the project from the date stated in the Notice to Proceed issued by the Parish.