

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Scope of work/Services

The Contractor shall provide all labor and materials to remove and replace existing 4' x 2'10" junction box and lid with a 3' x 4' x 3'6" traffic rated catch basin with traffic rated lid and 2'x 2' cast iron grate. Work shall be done per the LA DOTD Standard Specifications for Roads and Bridges, Sec. 702, 2016 Edition.

The Contractor shall also provide 10 LF of saw cut, 8" deep to remove a 2'6" x 5' area of road panel and intergraded gutter in front of the catch basin. The Contractor shall replace the concrete at the road panel, sloping it to allow water to drain into the new catch basin. The concrete shall be 8" thick LA DOTD Type B, 4000 psi with fiber mesh. Work shall include all necessary dowels to tie into the existing panel and be one per the LA DOTD Standard Specifications for Roads and Bridges, Sec. 602, 2016 Edition.

The Contractor shall remove and replace a 4' x 8'6" section of sidewalk, 4" thick to allow for construction of new catch basin. Work shall include all necessary saw cuts and be constructed of LA DOTD Type B concrete, 4000 psi with fiber mesh and be done per LA DOTD Standard Specifications for Roads and Bridges, Sec. 706, 2016 Edition.

The Contractor shall construct 5' of barrier curb, 6" wide and up to 8" tall, around the three sides of the catch basin. The curb shall taper down to match the grade and tie into the road panel mountable curb. The curb shall be constructed of LA DOTD Type B, 4000 psi concrete with fiber mesh and include all necessary re-bar and hoops to tie into the panel and catch basin lid. Work shall be done per LA DOTD Standard Specification for Roads and Bridges, Sec. 707, 2016 Edition.

The Contractor shall grade the existing slope, providing fill if needed and match the slope of the barrier curb. The Contractor shall supply and install sod to all disturbed areas. The Contractor shall remove all debris at no direct pay.

All supervision, labor, materials, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee **is not** required for this project.

The Contractor will have thirty (30) days to complete the project from the date stated in the Notice to Proceed issued by the Parish.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.