

**"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stp.gov.org](mailto:purchasing@stp.gov) to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."**

Work to Include:

Contractor to provide all labor, materials, equipment, and incidentals required to install a complete Lightning Surge Protection and Suppression System at the St. Tammany Parish Office of the Coroner facility located at 65278 Hwy 434 Lacombe, La. for the following area(s):

- Parking lot poles
- water storage tanks, and all;
- unprotected structures and electrical devices inside the chiller yard.

Work will include the addition of lightning dissipater's grounding rods on all unprotected structures and arresters on all currently unprotected electrical devices and circuits. The grounding rod system using copper clad ground rods, 3/4-inch diameter, ten (10) feet long shall be connected via an aluminum circuit system.

All equipment and materials shall be new, unused, and non-secondary market products. The contractor shall provide a one-year warranty on all workmanship and parts manufactory warranty periods from the completion of said work. The installation of the lightning protection system is required to be directly supervised by a UL trained, LPI certified, Master Installer.