"This is only the scope of work for the project. For more information, interested parties should contact Procurement at <u>purchasing@stpgov.org</u> to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

I. <u>Work to Include:</u>

The Contractor must provide all labor, equipment, tools, and materials necessary to improve the drainage system along the existing roadside ditches. Work to include removing/replacing driveway culverts, drainage pipes, concrete walks and driveways, excavation, installing catch basins, and concrete headwalls as specified along City Dr. (R09J050) in Slidell, Louisiana (Section 22 Township 9S Range 14E).

II. Location of Work:

City Dr. (R09J050) in Slidell, Louisiana (Section 22 Township 9S Range 14E).

III. <u>Documents:</u> Bid Documents dated April 5, 2018, and entitled:

City Dr. Drainage, Ph. 2 Bid No. 312-00-18-29-2

IV. <u>OTHER REQUIREMENTS</u> (as applicable)

When not otherwise specified herein, all work and materials shall conform to the requirements of the Louisiana Department of Transportation and Development hereafter called LDOTD (2006 Edition of Louisiana Standard Specifications for Roads and Bridges).