

THIS IS JUST A SCOPE OF WORK. PLEASE EMAIL PURCHASING@STPGOV.ORG FOR A COMPLETE PACKAGE.

Scope of work/Services

The Contractor shall provide all labor, materials and equipment necessary to saw cut, remove and replace existing concrete panels. The estimated concrete quantity is 167 square yards. The work shall also include all necessary pours, signage, traffic control and barricades.

Specifications for the concrete panels and curbs are as follows:

The concrete road panels are 8" thick and shall be constructed with 4000 psi concrete and doweled into adjoining panels with 5/8inch bars 24" on center. **The Contractor shall use an approved concrete accelerator as called out on LA DOTD QPL list to increase cure time.** The Contractor must maintain two lanes of traffic except for panels located before start of boulevard planter and at intersection of Citation and start of 75' long panel. The cost of additional pours to minimize lane closures shall be at no direct pay. The Contractor shall level and repair base as directed by inspector. The repaired areas are to receive A-4 select. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 602. The Contractor shall replace and seal joints in kind, i.e., construction or expansion joints. The work shall include all necessary saw cuts to adjoining panels to allow removal of panels to be replaced without damaging the adjoining panel and removal of temporary asphalt patch. The panel to be removed will be marked with white paint by inspector. All debris is to be removed at no direct pay.

Panel dimensions are as follows:

11' x 75'
8' x 30'
16' x 21'
6' x 16'

The Contractor is to verify all dimensions and lengths.

All work shall include all necessary signage, barricades and flagmen per LA DOTD Standard Specifications for Roads and Bridges, Section 713 and mobilization of equipment per Section 727. The Contractor shall notify residents and businesses of work prior to beginning of construction.

The Contractor will have thirty (30) days to complete the project from the date stated in the Notice to Proceed issued by the Parish.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.