

**This is just the scope of work. Please email the Procurement Department at [purchasing@stpgov.org](mailto:purchasing@stpgov.org) for more information.**

### **Scope of work/Services**

The Contractor shall provide all labor, materials and equipment necessary to saw cut and remove the existing concrete panel with integrated gutter, and replace widening turn radius as shown on the drawings. The estimated concrete quantity is 28 square yards. The work shall also include all necessary signage and barricades.

Specifications for the concrete panels and curbs are as follows:

The concrete road panels are 22' x 22' 7" x 8" radius with an integrated gutter, as shown in Attachment G Drawings, and shall be constructed with 4000 psi concrete and doweled into adjoining panels with 5/8" bars 24" on center. **The Contractor shall use an approved concrete accelerator as called out on LA DOTD QPL list to increase cure time.** The Contractor shall level and repair the base as directed by the Inspector. The repaired areas are to receive A-4 select. All work shall be performed in accordance with LA DOTD 2006 Standard Specifications for Roads and Bridges, Section 602. The Contractor shall replace and seal joints in kind, i.e., construction or expansion joints. The work shall include all necessary saw cuts to adjoining panels to allow removal of panels to be replaced without damaging the adjoining panel and removal of temporary asphalt patch. The panel to be removed will be marked with orange paint by the Inspector. All debris is to be removed at no direct pay. The Contractor is to verify all dimensions and lengths.

Work shall include all necessary signage, barricades and flagmen per LA DOTD 2006 Standard Specifications for Roads and Bridges, Section 713 and mobilization of equipment per Section 727. The Contractor shall notify residents and businesses of work prior to beginning of construction.

The Contractor will have 30 days to complete the project from the date stated in the Notice to Proceed issued by the Parish.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.