

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Contractor shall repair the catch basin located at 104 Eden Isles Blvd. (R09J009), Slidell, LA 70458 (S44-T09-R14).

Work shall include the following:

- Provide saw cut to remove top 10" from catch basin in order to rework from side inlet to drop inlet; and
- Provide and install traffic-rated concrete lid and traffic-rated cast iron grate. Lid dimensions are 2' wide x 4' long x 8" thick. Grate is to be 18" x 18".

All signage and barricades shall be provided and all debris shall be removed at no direct pay.

The time period to complete the work shall be thirty (30) calendar days from issuance of the Notice to Proceed (NTP) by the Parish.

All supervision, labor, materials, supplies, equipment, tools, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.