

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Scope of work/Services

Contractor shall repair headwall located at the southeast corner of Bentwood Drive (R03L106) at the intersection with Woodcrest Drive, Covington, LA 70433 (S11-T07-R11).

Work shall include providing and installing bricks to the broken portion of headwall. Dimensions are 8" x 8'3" x 8". Work shall include repairing lower section of bricks with grout and providing and installing 5/8 x 6" pins ever 2' O.C. and the removal of a 2' section of head wall that separated but did not fall off. All cracks shall be repaired and all three (3) sides of head wall shall be re-skimmed with Dayton Superior Re-Crete 20 minute grout or approved equal.

All signage and barricades shall be provided and all debris shall be removed at no direct pay.

The time period to complete the work shall be thirty (30) calendar days from issuance of the Notice to Proceed by the Parish.

All supervision, labor, materials, supplies, equipment, tools, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee is not required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.