

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stp.gov.org](mailto:purchasing@stp.gov) to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

The Contractor must provide all labor, equipment, tools and materials to improve drainage by removing the existing CB-07 catch basin and replace with a new CB-07 catch basin. Interior basin dimensions are 50" long x 30" wide x 36' deep and is to be either cast in place or constructed with 8" concrete brick modules. The Contractor shall provide and install a new traffic rated lid and CB-07 lid, grate and frame. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 702, 2016 Edition.

All debris shall be removed at no direct pay. Work shall include all necessary signage, barricades and flagmen per LA DOTD Standard Specifications for Roads and Bridges, Sec. 713, 2016 Edition and mobilization of equipment per section 727. The Contractor shall verify dimensions.

Time period for completion of the work is thirty (30) days from issuance of the Notice to Proceed by the Parish. All supervision, labor, materials, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee is not required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.