

This is only the scope of work for the project. For more information, please contact Procurement at purchasing@stpgov.org

The Contractor must saw cut the road and remove the culvert that is under the roadway on Autumn Dr at the intersection of Fall Rd. The Contractor must remove the mail boxes and the sidewalk; install new culverts [18" x 28" RCPA] on a 6" bed of crushed concrete and backfill 8" below the asphalt paving with crushed concrete; install 72' of 18" x 28" RCPA culverts going north west on the northeast side of roadway; install 2 4' x 4' precast catch basins with a 2' x 2' traffic rated cast iron drop in grate; wrap all culvert joints; install 78 cubic yards of embankment over the sub surface pipe; replace the concrete sidewalk; install all mail boxes; and replace the asphalt where the saw cut was and a 20' turning radius, [60 square yards asphalt].