

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stp.gov.org](mailto:purchasing@stp.gov) to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Scope of work/Services

Contractor shall provide all labor, tools, equipment, and materials necessary to install subsurface drainage to the west parking lot of the Justice Center and within the adjacent property per the drawing/specifications (Attachment "A"). The subsurface drainage work shall include but is not limited to the following:

- Removal of concrete catch basin;
- Removal of pipe (storm drain);
- Barrow (net section);
- Aggregate surface course(net section);
- Storm drain pipe arch (15" Equiv.RCPA);
- 12" storm drain pipe (A-2000);
- Yard drain pipe (6" PVC);
- Pipe fittings (tee inlet);
- Catch basin (CB-01);
- Catch basin (CB-04);
- concrete walk (4" thick);
- Incidental concrete paving (4" thick);
- Slab sodding (match existing);
- Bedding material;
- Mobilization; and
- Construction layout.

At the completion of the installation, all disturbed surfaces shall be restored to the original condition including but not limited to re-sodding of lawn and replacement of concrete sidewalks.

Contractor shall provide all signage and barricades and all debris shall be removed at no direct pay. All required federal, state and local permit applications, fees, and approvals shall be the responsibility of the awarded Contractor.