

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Contractor shall improve drainage at 106 Turtle Creek Blvd. (R08N078), Slidell, LA 70461 (S37-T9-R15). Work shall include removing and replacing the existing catch basin (CB-07) and concrete portion of the lid. The cast iron components (lid, frame and grate) of the existing catch basin (CB-07) are to be re-used. Work shall include providing 4' of .83' ductile steel sleeve to go around an existing .67' sewer force main that runs through the box and providing 7 linear feet of concrete saw cutting, .67' deep. The catch basin shall be traffic-rated and the lid reinforced with #8 re-bar on 1' centers where running under the road way. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 702, 2016 Edition.

Work shall also include removing and reinstalling 6' of .5' x 1' mountable curb. Work shall include all saw cuts and hoops necessary to install. Curb shall be constructed with 4000 psi LA DOTD Type B concrete with fiber mesh. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 707, 2016 Edition.

All disturbed areas shall have sod provided and installed. All signage and barricades shall be provided and all debris shall be removed at no direct pay.

The time period to complete the work shall be thirty (30) calendar days from issuance of the NTP by the Parish.

All supervision, labor, materials, tools, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.