

**"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stpgov.org](mailto:purchasing@stpgov.org) to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."**

### **Scope of work/Services**

One 15' x 13' road panel located 250' West of the intersection with Lakeshore Blvd North on the south side of the east bound lane of Lakeshore Boulevard East, Slidell, LA (S34-T09S-R14E) shall be removed and replaced. The replacement panel is to be constructed of 4000 psi Class B concrete with fiber mesh and ¾" dowels set at 2' centers. Asphalt impregnated fiber board shall be installed on each end of the panel and joints sealed with an approved sealer. All work shall be done in accordance with LA DOTD Standard Specifications for roads and Bridges, Sec. 602, 2016 Edition. The base shall be leveled and repaired with A-4 select as specified by the Parish.

A new cast iron grate and frame shall be provided and installed. Frame and cast iron grate shall be of same shape as units currently in the curb and roadway. An 8" thick concrete lid for frame and grate constructed of 4000 psi Class B concrete with fiber mesh shall be provided and installed. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 702, 2016 edition.

41 LF of 6" x 14" mountable curb shall be removed and replaced. Mountable curb is to be constructed of 4000 psi Class B concrete with fiber mesh. All necessary saw cuts and rebar hoop to remove and construct curb shall be supplied. Control joints shall be tooled into the mountable curb where it spans over a panel joint. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 707, 2016 Edition.

All dimensions and work shall be field verified. All signage and barricades shall be provided and all debris shall be removed at no direct pay.

The time period to complete the work shall be thirty (30) calendar days from issuance of the Notice to Proceed (NTP) by the Parish.

All supervision, labor, materials, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.