

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stp.gov.org](mailto:purchasing@stp.gov) to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Scope of work/Services

The Contractor must provide all labor and materials to install a 2" lift of asphalt over the concrete driveway apron to alleviate standing water at the apron. This will require grinding a transition of approximately 2" deep and at least 2' wide by 25' long into the concrete for a clean tie-in with asphalt. "Tack" flat and vertical surfaces where asphalt is to be laid. The edge of the street will need saw cutting where damaged (approximately 40'). Install a 2" lift of asphalt over the concrete apron except at the road's edge, which will be at least 6" thick. The driveway is approximately 36 SY from the edge of the street to the first joint. This is an ingress/egress driveway apron. Driveway is located on Pete Foster Rd. approximately 406' from Hwy 190.

All debris shall be removed at no direct pay. The Contractor shall provide all signage and barricades. All supervision, labor, materials, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

The Contractor shall have thirty (30) days to complete project upon issuance of the Notice to Proceed by the Department of Public Works.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.