

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stp.gov.org](mailto:purchasing@stp.gov) to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

I. Work to Include:

The Contractor must provide all labor, equipment, tools, and materials necessary to perform the following:

- Clearing and grubbing of the new right-of-way, including stripping topsoil, grubbing, and hauling off of trees, vegetation, and topsoil;
- Construction of a two lane undivided roadway, cul-de-sac(s), and driveways, including roadway/driveway base and sub-base, striping, and signage;
- Construction of roadside ditches, including culverts and sweeping of an existing ditch;
- Removal of existing asphalt, including temporary stockpiling and haul-off;
- Construction of a right turn lane from Brewster Road to Christwood Boulevard Extension, including pavement base and sub-base, curb and gutter, striping and signage; and
- Other items as shown on the plans, specifications and supplemental specifications.