

Quote # 015-45-18-42-1 - Logan Ln Panel Repairs

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Contractor shall remove and replace (2) concrete road panels at 1881 Logan Ln. (R04D175), Mandeville, LA 70448 (S40-T08-R11). Panels are approximately 10' x 21' each and shall be constructed of 4000 psi "High Early" Class B concrete 8" thick. Work shall include the installation of 0.5' x 1' x 0/1 wire mesh throughout the panel and 3/4" dowels on 2' centers. Work shall include all necessary saw cuts to remove the panels. Contractor shall supply and install asphalt impregnated fiber board on each end of the panel and seal the joints. Contractor shall level and repair road base as needed with granular material compacted to 95% of the standard proctor.

All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 602 2016 Edition.

All debris shall be removed at no direct pay. All traffic control and devices shall be provided and set up per the LA DOTD TTC and MUTCD details.

The time period to complete the work shall be thirty (30) calendar days from issuance of the NTP by the Parish.