

**THIS IS JUST A SCOPE OF WORK. PLEASE EMAIL [PURCHASING@STPGOV.ORG](mailto:PURCHASING@STPGOV.ORG) FOR A COMPLETE PACKAGE.**

### **Scope of work/Services**

The Contractor must provide all labor, equipment and materials necessary to remove and replace two (2) CB-07 catch basins, one (1) 4' x 4' catch basin, 107 lf of curb and gutter; remove and reset 43 square feet of brick pavers; provide and install 10 Cubic Yards of 610 stone and 186 square yards of 12" asphalt base repair and 2" asphalt wearing course. The Contractor must clean, repair and seal seven (7) culvert joints and one (1) junction box and replace sod where it is disturbed. Mobilization and all associated costs must be included in each unit item. See Specification Sheets Dated 3/29/17.

The Contractor will have thirty (30) days to complete the project from the date stated in the Notice to Proceed issued by the Parish.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.