

THIS IS JUST A SCOPE OF WORK. PLEASE EMAIL PURCHASING@STPGOV.ORG FOR A COMPLETE PACKAGE.

Scope of work/Services

The Contractor shall provide all materials and labor necessary to install 40 SQYD of concrete cast-in-place revetment and associated excavation and embankment along the roadside ditch on the northeast corner of the intersection of Meadows Blvd and Madison Ln. The Contractor shall also remove riprap and install sod at any locations disturbed due to construction.

Specification for the concrete cast-in-place revetment is as follows:

The concrete cast-in-place revetment shall be Class M concrete 4" thick with a minimum 3000 psi. All work shall be done in accordance with LADOTD Standard Specifications for Roads and Bridges, Section 712. Reference LADOTD Special Detail PD-01 for concrete cast-in-place revetment details. The Contractor is to verify all dimensions and lengths.

The work shall include all necessary signage, barricades and flagmen per LA DOTD Standard Specifications for Roads and Bridges, Section 713 and mobilization of equipment per Section 727.

The Contractor will have 30 days to complete the project from the date stated in the Notice to Proceed issued by the Parish.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.