

THIS IS JUST A SCOPE OF WORK. PLEASE EMAIL PURCHASING@STPGOV.ORG FOR A COMPLETED PACKAGE.

Scope of work/Services

The Contractor will provide all labor and materials necessary to remove an existing 13' of 24" CMP and replace it with a 14' of 24" A-2000 culvert at Bamboo and Crestwood Blvd. The work shall also include reworking and sealing the side of the existing catch basin to accommodate the A-2000 pipe, building a concrete headwall and providing sod to all disturbed areas.

Specifications for the head wall are as follows:

The head wall construction is to be 4000 PSI concrete and include 5/8 re-bar. The dimensions for the head wall are 14' wide by 4' tall and 6" thick. The head wall shall extend 6" below bottom of the culvert. The work shall include all excavation, back fill and compaction of soil around the headwall. All work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Section 805. All debris is to be removed at no direct pay. Measurements are approximate and to be verified by the Contractor.

The work shall include all necessary signage, barricades and flagmen per LA DOTD Standard Specifications for Roads and Bridges, Section 713 and mobilization per Section 727.

The Contractor will have thirty (30) days to complete the project from the date stated in the Notice to Proceed issued by the Parish.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.