

**THIS IS JUST A SCOPE OF WORK. PLEASE EMAIL
PURCHASING@STPGOV.ORG FOR A COMPLETE PACKAGE.**

2.1 Scope of work/Services

The Contractor will provide all labor and materials to remove and replace two (2) catch basins and cast iron grates located at 1102 and 1130 Belair Blvd. The work shall also include removal and replacement of a 6' tall wooden fence, 18 feet long and the installation of both seed and fertilizer and wood mulch at disturbed areas.

Specifications for the catch basin are as follows:

The catch basin is to either be cast in place or constructed out of concrete modular blocks. The lid shall be 8" thick, include an 18" x 18" cast iron grate and is to be set lower than adjacent grade to allow water to drain. The catch basin dimensions are 4' x 4' wide and 2' 6" deep and will accommodate two (2) 10" PVC storm drain pipes. The work shall include all excavation, back fill and compaction of soil around box. All work shall be performed in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Section 706. The Contractor is responsible for dressing any ruts or damage to yard occurring as a result of construction at no direct pay. All debris is to be removed at no direct pay. Measurements are approximate and to be verified by the Contractor.

The work shall include all necessary signage, barricades and flagmen per LA DOTD Standard Specifications for Roads and Bridges, Section 713 and mobilization per Section 727.

The Contractor will have 30 days to complete the project from the date stated in the Notice to Proceed issued by the Parish.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.