

**THIS IS JUST A SCOPE OF WORK. PLEASE EMAIL
PURCHASING@STPGOV.ORG FOR A COMPLETE PACKAGE.**

The Contractor shall provide and install two (2) CB-01 catch basins with wire grates. Work shall also include excavation and all necessary cuts to A-2000 drainage pipes in order to install boxes. The Contractor shall back fill and compact surrounding ground and grade to allow drainage to catch Basin. The Contractor shall sod all disturbed areas.

Specifications for the catch basins are as follows:

Catch basins are to be model CB-01 with wire grates and be set 2/10ths lower than adjacent grade to allow water to drain. Catch basins shall be large enough to accommodate 24" A-2000 pipe with inverts of 3' 9 13/16th" and 3' 6 13/16th". Contractor shall expose and cut A-2000 pipe as needed to install boxes. Work shall include all excavation, back fill and compaction of soil around box. All work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Section 706. All debris is to be removed at no direct pay.

Measurements are approximate and to be verified by Contractor.

Work shall include all necessary signage, barricades and flagmen per LA DOTD Standard Specifications for Roads and Bridges, Section 713 and mobilization per Section 727.

The Contractor will have 30 days to complete the project from the date stated in the Notice to Proceed issued by the Parish.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.