

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full bid package, to be listed as a plan holder and to ensure any addenda to the bid package are received."

The work specified in this project requires the removal and replacement of thirty-eight (38) linear feet of damaged guard rail including the collapsible end, tangent termination and all posts, mounting blocks and hardware required for installation on the Service Road Bridge (B08L020) approximately 2800 ft. south of Lake Village Boulevard on the I-10 Service Road, Slidell, LA (S36-T08-R15). Guard rails are to be galvanized thrie-beam and posts are to be galvanized I-beam, 4"x 6" with 1/4" legs and 3/8" webbing. Additionally, ten (10) feet of thrie-beam, one (1) mounting block and one (1) post to be located and identified by the Parish shall be supplied and installed. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 704, 2016 Edition.

All signage and barricades shall be provided and all debris shall be removed at no direct pay.

The time period to complete the work shall be thirty (30) calendar days from issuance of the Notice to Proceed (NTP) by the Parish.

All supervision, labor, materials, tools, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.