

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full bid package, to be listed as a plan holder and to ensure any addenda to the bid package are received."

The Contractor must provide all labor, equipment, tools and materials to improve road and drainage by removing and replacing four (4) concrete road panels. Panels are to be 8" thick and constructed with 4000 PSI Type B concrete with fiber mesh and ¾" dowels on 24" centers. Two (2) panels at 15.67' x 13.00' and two (2) panels are 14.5' x 13.00'. All four panels have a 6" x 12" mountable curb. The Contractor shall provide all necessary saw cuts to remove the panels without damaging adjoining panels and level and repair the base with A-4 select as directed by the inspector. All work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Sec. 602, 2016 Edition. All joints are to be sealed. Remove and replace 49 LF of 6" x 12" mountable curb. Curbs are to be constructed of 4000 PSI Type B concrete with fiber mesh and include all hoops required to install onto existing concrete panels. The Contractor shall tool expansion joints into the curb where they fall over joints in the existing concrete. All work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Sec. 707, 2016 Edition. Remove and Replace one (1) CB-07 catch basin. Catch basin dimensions are 2.5' x 4.5'. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 702, 2016 Edition. The Contractor shall re-use the existing frame and cover. Clean, repair and reseal one (1) catch basin. The Contractor shall use Re-Crete 20 minute grout by Dayton Superior or prior approved equal. Excavate and expose pipe joint under panels to be removed and wrap with geotextile fabric. Back fill and compact area around pipe joints.

All panels and curb to be replaced will be marked by the inspector in orange paint.

All debris shall be removed at no direct pay. The Contractor shall provide all signage and barricades.

Time period for completion of the work is thirty (30) days from Notice to Proceed issued by the Parish.

All supervision, labor, materials, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee is not required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.