

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stp.gov.org](mailto:purchasing@stp.gov) to ensure receipt of a full bid package, to be listed as a plan holder and to ensure any addenda to the bid package are received."

The contractor shall provide all labor, materials and equipment necessary to remove and replace five (5) concrete road panels on Riviera Dr. and nine (9) concrete road panels and 115'4" of 6" x 6" barrier curb on St. Andrews Ct.

Specifications for the concrete panels and curbs are as follows:

Concrete road panels are 8" thick and shall be constructed with 4000 PSI concrete and doweled into adjoining panels with 5/8th bars 24" on center. The contractor shall level and repair base as directed by inspector. Repaired areas are to receive A-4 select. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 602. The contractor shall replace and seal joints in kind, ie, construction or expansion joints. Work shall include all necessary saw cuts to adjoining panels to allow removal of panels to be replaced without damaging the adjoining panel and removal of temporary asphalt patch. Panel to be removed will be marked with orange paint by inspector. All debris is to be removed at no direct pay

Concrete barrier curbs are to be 6" tall by 6" wide and constructed with 4000 PSI concrete. Work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Section 707. Work shall include all necessary saw cuts to remove curb. Asphalt impregnated fiber board shall be installed in control joints that are located above a road panel construction and expansion joints. Curbs to be replaced will be marked in paint by the inspector. All debris is to be removed at no direct pay.

Locations and dimensions for Riviera are as follows:

108 Riviera 13'9" x 16' x 12' 5"

13'9" x 16' x 12'5"

110 Riviera 14' x 12' 5"

201 Riviera 15' 2" x 12' 5"

12' 10" x 12' 5"

14' 4" x 12' 5"

St. Andrew Ct. See attached drawing.

The Contractor is to verify all dimensions and lengths.

Work shall include all necessary signage, barricades and flagmen per LA DOTD Standard Specifications for Roads and Bridges, Section 713 and mobilization of equipment per Section 727. Contractor shall notify residents and businesses of work prior to beginning of construction.

The contractor will have 30 days to complete the project from the date stated in the Notice to Proceed issued by the Parish.

A Quote Guarantee **is** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.