

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

This is a Capital Improvements Project. The work specified in this project will require the Contractor to have all necessary labor, tools and equipment to perform the following work:

The Contractor must saw cut, remove and replace 31 Square Yards of 8" concrete road panel and 6" x 12" mountable curb, poured monolithically. The Contractor must remove and replace an additional 33' 6" of 6" x 12" mountable curb. The Contractor shall provide and install all required hoops and control joints over existing panel joints and remove and replace 12 Square Yards of 8" concrete spandrel area. They must clean, repair and reseal both interior and exterior of existing CB-07 catch basin with Dayton Superior Re-crete 20 minute grout or approved equal. They must also provide and install .5 Cubic Yards of crushed stone in sink hole, installing and compacting in 12" lifts.

Removal of all debris is to be done at no direct pay. The Contractor is responsible to verify all quantities.

The time period for completion of the project is thirty (30) calendar days from Notice to Proceed issued by the Parish.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.