

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stp.gov.org](mailto:purchasing@stp.gov) to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Contractor must provide all labor, materials, tools, and equipment to repair the drainage as described in the specification along Timbercreek Ln(R04D148; S-41-T7-R11) in Mandeville, Louisiana 70448.

Contractor shall remove existing splash pad, provide and install catch basin with cast iron grate, install a splash pad around the basin, back fill and grade around catch basin. Work shall include installing sod to all distributed areas.

Contractor shall provide all signage and barricades and all debris shall be removed at no direct pay.

Contractor will be required to complete the work within (30) calendar days from Notice to Proceed issued by the Parish.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.