

Quote #015-35-18-38-1 - Clayton Ct Panel & Curb Repairs

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Contractor will repair concrete panels and curbing located at 424 Clayton Court (R08N093), Slidell, LA 70461 (S37-T9-R15).

Contractor shall remove and replace concrete road panels and mountable curb. Panel dimensions are approximately: 12' x 14'6" x 8"; 12' x 15'2" x 8"; and 13' x 15' x 8" and include the 6" x 12" mountable curb. An additional 16' of 6" x 12" mountable curb will also be replaced. Panels and mountable curb are to be constructed of 4000 psi Class B concrete with fiber mesh.

Work shall include all necessary saw cuts to remove panels and curbs, re-bar hoops and 3/4" dowels. All expansion joints and sealers are to be replaced in kind.

All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 602, 2016 Edition.

Contractor shall provide all signage and barricades and all debris shall be removed at no direct pay.

The time period for completion of the work shall be thirty (30) calendar days from the issuance of the Notice to Proceed by the Parish.