

**"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stpgov.org](mailto:purchasing@stpgov.org) to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."**

This is a Capital Improvement Project. The work specified in this project will require the Contractor to supply all labor, equipment and materials to remove and replace one (1) concrete driveway. Driveway is to be 6" thick and constructed with 3000 psi, Class M concrete. Driveway dimensions are 21'6" at the road, 10'4" deep and 16'1" at the rear of the drive. The Contractor shall provide a weakened plane down the center of the driveway. All work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Section 706, 2016 Edition.

All debris shall be removed at no direct pay.

The contractor shall have thirty (30) days to complete project upon issuance of the Notice to Proceed by the Parish.

All supervision, labor, materials, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee **is not** required for this project.