

**"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stpgov.org](mailto:purchasing@stpgov.org) to ensure receipt of a full bid package, to be listed as a plan holder and to ensure any addenda to the bid package are received."**

Contractor shall provide all labor and materials necessary to remove and replace 20 square yards of concrete road panel with mountable curb and install 6" x 12" mountable curb along Airport Rd (R09-C-037) at Intersection with Amber Trace entrance, Slidell, LA (S33-T8-R14).

The panel and curbing to be replaced is on the southwest corner of the entrance drive to Amber Trace off of Airport Rd.

The 20 square yards of 8" thick concrete road panel shall be constructed of 4000 psi Class B concrete, containing mesh fibers. The road panel shall include 6" x 12" mountable curb and all necessary saw cuts to remove and replace the panel. The Contractor shall level and repair the base with A-4 select material. This portion of the work shall be in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 602, 2016 Edition.

The additional 6" x 12" x 6' mountable curbing shall be constructed of 4000 psi Class B concrete with fibers and shall include the supply and installation of all required rebar hoops. This portion of the work shall be in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 707, 2016 Edition.

The Contractor shall remove the limestone and install embankment and sod over the end of the pipe. The embankment shall be compacted in place and the sod shall be green and free of brown spots or insect damage.

Contractor shall provide all signage and barricades, and all debris shall be removed at no direct pay.

The time period to complete the work shall be thirty (30) calendar days from issuance of the NTP by the Parish.

All supervision, labor, materials, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.