

**"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stpgov.org](mailto:purchasing@stpgov.org) to ensure receipt of a full bid package, to be listed as a plan holder and to ensure any addenda to the bid package are received."**

Contractor shall clean, repair, and reseal the catch basin, and remove and replace the damaged concrete panel and curbing on Denmark Court (R08V064) in Slidell, Louisiana 70461 (S24-T09-R14).

72 square yards of concrete road panels shall be removed and replaced. Panels are to be 8" thick and constructed of 4000 psi Class B concrete with fiber mesh.  $\frac{3}{4}$ " dowels 2" on center shall be supplied and installed. All saw cuts necessary to remove the panels shall be supplied. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 602, 2016 Edition. Base shall be leveled and repaired prior to placing the concrete. All wet areas shall be replaced with A-4 select granular material as identified by the Parish.

41 linear feet of 7" x 14" concrete mountable curb shall be removed and replaced. The curb shall be constructed of 4000 psi class B concrete with fiber mesh. All saw cuts to remove the curb shall be supplied. All necessary re-bar hoops shall be supplied and installed. Control joints shall be tooled into the curb where it crosses a joint in the panel. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 707, 2016 Edition.

Existing catch basin shall be cleaned, all cracks repaired, and resealed. The basin shall be repaired and sealed with Dayton Superior Re-Crete 20 minute grout or approved equal.

All signage and barricades shall be provided and all debris shall be removed at no direct pay.

The time period to complete the work shall be thirty (30) calendar days from issuance of the Notice to Proceed (NTP) by the Parish.

All supervision, labor, materials, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.