

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full bid package, to be listed as a plan holder and to ensure any addenda to the bid package are received."

Damaged mountable curbs shall be repaired as follows:

- remove and replace 112'6" of 6" mountable curb between 1434 and 1442 Hillary Drive, Slidell, LA 70461; and
- remove and replace 52' of 6" mountable curb between 1518 and 1522 Hillary Drive, Slidell, LA 70461.

All curbs are to be 6 inches tall by 12 inches wide and constructed with 4000 psi Class B concrete. All saw cuts to remove the curbs and install re-bar hoops shall be provided as needed. Control joints shall be tooled into the curb when it covers a control or construction joint in the road panel. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges Section 707, 2016 edition.

All signage and barricades shall be provided and all debris shall be removed at no direct pay.

The time period to complete the work shall be thirty (30) calendar days from issuance of the Notice to Proceed (NTP) by the Parish.

All supervision, labor, materials, tools, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.