

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stp.gov.org](mailto:purchasing@stp.gov) to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Contractor shall provide and install traffic rated catch basin and cast iron frame and grate located at Tenth St (R03K001) in Covington, Louisiana (Section 42 Township 7 Range 11). Catch basin dimensions are to be 36"x36" with an 8" traffic rated lid. The invert top of the lid to bottom of the pipe shall be 23". Work shall be done per the LA DOTD Standard Specifications for Roads and Bridges, Section 704, 2016 Edition. The Contractor shall supply backfill and compact around the catch basin with granular material. The Contractor shall provide a 4" PVC stub out from the basin extending 4' towards the home. The Contractor shall set the pipe 12" lower than the existing grade at the yard drain. All debris shall be removed at no direct pay.

The time period for completion of the project is thirty (30) calendar days from Notice to Proceed issued by the Parish.

All supervision, labor, materials, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.

A Quote Guarantee **is not** required for this project.