



ST. TAMMANY PARISH

MICHAEL B. COOPER
PARISH PRESIDENT

March 1, 2021

Please find the following addendum to the below mentioned BID.

Addendum No.: 1

Bid#: 21-5-2

Project Name: Parishwide Sinkhole Repairs

Bid Due Date: Wednesday, March 10, 2021

GENERAL INFORMATION:

1. **Replace** "Frost Ln. Specification" with "Frost Ln. Specification Revised" (Attached)
 - Item 701-03-02042 quantity has decreased from 265 to 170.
2. **Replace** "Unit Price Form" with "Unit Price Form Revised" (Attached)
 - Ref No.: 701-03-02042 has decreased from 265 to 170.

ATTACHMENTS:

1. Frost Ln. Specification Sheet – Revised.pdf
2. Unit Price Form – Revised.pdf

End of Addendum # 1

201 Frost Ln. in Greenleaves Subdivision Revised 2-22-21

Item	Description	Length	Width	Quantity	Unit
	<p>General Notes:</p> <ol style="list-style-type: none"> 1. Contractor shall field verify all quantities and measurements. 2. Contractor shall be responsible for locating and protecting all existing utilities. 3. Two-way traffic shall be maintained at all times during construction. 4. Prior to beginning work, contractor will provide temporary signs and barricades at no direct pay: furnish, install, maintain and remove temporary signs, construction signs and / or barricades; and provide flagmen to comply with all other requirements regarding the projection of the work, workers and safety of the public. Work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 713. 5. Driveway aprons shall be tied-in to existing hard surfaced drives or extend two (2) feet behind the culvert, whichever is greater. For clarification purposes, tie-in new asphalt to existing asphalt/concrete aprons at no direct pay. 6. All turning radii shall be a minimum of thirty-five (35) feet. 7. All existing sewer lines shall be tied-in at no direct pay. 8. For clarification purposes, tie-in new asphalt to existing asphalt aprons at no direct pay on existing gravel roads. 9. Any <i>additional work</i> performed by the contractor <i>without prior written approval</i> from the St Tammany Parish Department of Public Works, the cost of the work will be borne by the contractor and will not be reimbursed by the Parish. 				
	<p>Project Summary: All labor and materials necessary to remove and replace the existing cmp culvert, drop inlets and headwall. Work also includes removing and replacing the wood fence, the removal of trees and the installation of sod to all disturbed areas.</p>				
<p>727-01-01000</p>	<p>Mobilization: All labor and materials necessary to accomplish preparatory work and operations, including those necessary for movement of personnel, equipment, supplies and incidentals to the project site. Mobilization costs shall follow rules called out in the LA DOTD Standard Specifications for Roads and Bridges, Sec. 727.</p>			<p>1</p>	<p>Lump Sum</p>

201 Frost Ln. in Greenleaves Subdivision Revised 2-22-21

Item	Description	Length	Width	Quantity	Unit
701-03-02042	30" PCCMP Culvert: All labor and materials necessary to provide and install 30" Polymer Coated Corrugated Metal Culverts (PCCMP) culverts. Work shall include supplying all necessary straps and bands and wrapping the joints in appropriate geotextile fabric. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 701, 2016 Edition. All debris is to be removed at no direct pay.			170	Linear Foot
701-12-01040	18" Drop Inlet: All labor and materials necessary to fabricate and install (2) 18" diameter Stacks out of PCCMP. Stack shall be installed by the manufacture providing the 30" PCCMP. The stacks shall be located in the same spot as the originals. The contractor shall provide a 18" diameter cast iron grate a 36" x 36" x 4" Splash pad around the stack. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 701, 2016 Edition. All debris shall be removed at no direct pay.			2	Each
805-01-01000	Concrete Headwall: All labor and materials necessary to remove and replace the existing head wall. The head wall is to be 4' tall by 6' wide and 6" thick. The structure is to be constructed of 4000 psi concrete with fibers. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 805. All debris is to be remove at no direct pay.			1	Each
714-01-00700	Sod: All Labor and materials necessary to provide and install Sod to all disturbed areas. Ground shall be compacted, shaped and graded prior to placement of seed. All work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Sec. 714. All debris is to be removed at no direct pay.			1	Lump Sum
202-02-00010	Tree Removal: All labor and materials necessary to remove (2) trees and roots. Trees are ornamental and 6" or less in diameter. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 202, 2016 Edition. All debris shall be removed at no direct pay.			2	Each

All Work Shall Conform to Louisiana Standard Specifications for Roads and Bridges, Latest Edition

201 Frost Ln. in Greenleaves Subdivision Revised 2-22-21

Item	Description	Length	Width	Quantity	Unit
705-09-00100	Remove and Replace Wood Fence: All labor and material necessary to remove and replace existing wood fence. Works shall include replacement of any gates and hardware that are existing. The contractor shall confirm that there are no animals in the yard before removing. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 705, 2016 Edition. All debris shall be removed at no direct pay.			99	Linear Foot

LOUISIANA UNIFORM PUBLIC WORK BID FORM UNIT PRICE FORM REVISED

TO:

St. Tammany Parish Government

21454 Koop Drive, Suite 2F

Mandeville, LA. 70471

(OWNER TO PROVIDE NAME AND ADDRESS OF OWNER)

BID FOR:

Parishwide Sinkhole Repairs

Revised 2-22-21

(OWNER TO PROVIDE PROJECT NAME & OTHER IDENTIFYING INFO)

UNIT PRICES: This form shall be used for any & all work required by the Bidding Documents & described as unit prices. Amounts shall be stated in figures & only in figures.

Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # Mobilization				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
727-01-01000	1	Lump Sum		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # Tree Removal				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
202-02-0010	2	Each		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # Granular Fill				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
203-04-00200	13	Cubic Yard		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # Crushed Stone				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
302-01-00300	4	Cubic Yard		

Wording for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.

UNIT PRICES: This form shall be used for any & all work required by the Bidding Documents & described as unit prices. Amounts shall be stated in figures & only in figures.

Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # 8" Concrete Road Panel				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
602-05-03120	391	Square Yard		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # 30" PCCMP Culvert				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
701-03-02042	170	Linear Feet		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # 18" Drop Inlet				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
701-12-01040	2	Each		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # CB-07 Catch Basin				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
702-03-00600	8	Each		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # Rework Top Half of CB-07				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
702-03-00601	1	Each		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # Recast CB-07 Lid				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
702-03-00602	1	Each		

Version 2017 Q2

Wording for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.

UNIT PRICES: This form shall be used for any & all work required by the Bidding Documents & described as unit prices. Amounts shall be stated in figures & only in figures.

Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # Remove & Replace Wood Fence				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
705-09-00100	99	Linear Feet		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # 4" Concrete Sidewalk				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
706-01-00100	40	Square Yard		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # 6" Concrete Drive				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
706-02-00200	65	Square Yard		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # 8" Drain Apron				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
706-03-00500	3	Square Yard		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # 6" x 12" Mountable Curb				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
707-01-00100	142	Linear Feet		
Description: <input type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT #				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)

Version 2017 Q2

Wording for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.

UNIT PRICES: This form shall be used for any & all work required by the Bidding Documents & described as unit prices. Amounts shall be stated in figures & only in figures.

Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # Flowable Fill				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
710-01-00100	3	Cubic Yard		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # Sod				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
714-01-00700	1	Lump Sum		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # Concrete Headwall				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
805-01-0100	1	Each		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # Clean, Repair and Reseal Drainage Structure				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
S-001	12	Each		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # Reseal & Wrap Culvert Joints with Fabric				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
S-002	16	Each		
Description: <input checked="" type="checkbox"/> BASE BID OR <input type="checkbox"/> ALT # Clean, Repair and Reseal Culvert Joints				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
S-003	91	Each		

Version 2017 Q2

Wording for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.