



## ST. TAMMANY PARISH

PATRICIA P. BRISTER  
PARISH PRESIDENT

**January 24, 2019**

Please find the following addendum to the below mentioned BID.

**Addendum No.:** 1

**Bid#:** 300-00-18-64-2

**Project Name:** Rousseau Rd Improvements

**Bid Due Date:** Tuesday, January 29, 2019

### **QUESTIONS & ANSWERS:**

---

Question 1: On page 2a of the plans the bottom typical section shows to place the new geotextile fabric and class II base course on the existing subbase. On plan page 3 it has a quantity of 3848 SY of asphalt to be removed in this section, is this correct that the existing roadway is getting removed under the removal of asphalt pavement and the general excavation item?

Answer 1: From station 69+84 to 106+00 the removal of surfacing and stabilized base item shall pay for the removal of the existing road and base. From station 106+00 to 124+89 the removal of asphalt pavement and general excavation items shall pay for removal of the existing road and base.

**End of Addendum #1**