



## ST. TAMMANY PARISH

MICHAEL B. COOPER  
PARISH PRESIDENT

**April 1, 2022**

Please find the following addendum to the below mentioned QUOTE.

**Addendum No.:** 1

**Quote#:**22-14-1

**Project Name:** Blue Crane No.1 Drive Drainage Repair

**Quote Due Date:** Thursday, April 26, 2022

### GENERAL INFORMATION:

---

1. Please replace Notice to Quoters – with “Notice to Quoters Revised.” (attached)
2. Please replace 237 Blue Crane No.1 Drive Sinkhole Repair - with “237 Blue Crane No.1 Drive Drainage Repair Revised Addendum #1” (attached)

### ATTACHMENTS:

---

1. **Notice to Quoters Revised.pdf**
2. **237 Blue Crane No.1 Drive Drainage Repair Revised Addendum #1.pdf**

**End of Addendum #1**



## ST. TAMMANY PARISH

MICHAEL B. COOPER  
PARISH PRESIDENT

# NOTICE OF QUOTE REQUEST-REVISED

## ST. TAMMANY PARISH

Sealed quotes will be received by the Department of Procurement, until **2:00 p.m., Tuesday, April 26, 2022** and then opened at that time by the Procurement Staff for the following project:

### Quote # 22-14-1 – Blue Crane No.1 Drive Drainage Repair

This Quote package is available online at:

- St. Tammany Parish Government Website: <http://www.stpgov.org/>
- Bid Express Website: <http://www.bidexpress.com/>
- LaPAC – Louisiana Procurement and Contract Network:

<https://wwwcfprd.doa.louisiana.gov/osp/lapac/dspBid.cfm?search=department&term=185>

**NOTE:** LaPAC is the State’s online electronic solicitation notification system on the Office of State Procurement website. LaPAC provides an immediate e-mail notification to subscribing vendors of a STPGOV solicitation and any addenda posted. To receive the e-mail notification, vendors must register in the LaGov portal. Registration is intuitive at the following link:

[https://lagoverpvendor.doa.louisiana.gov/irj/portal/anonymous?guest\\_user=self\\_reg](https://lagoverpvendor.doa.louisiana.gov/irj/portal/anonymous?guest_user=self_reg)

It is the Vendor’s responsibility to check the Parish website frequently for any possible addenda that may be issued. The Parish is not responsible for a Vendor’s failure to download any addenda documents required to complete a submission.

Each Quote must be sealed. In addition, the outside of the envelope, box or package containing the Quote should be marked with the following information. Name and Address, State Contractor’s License Number (if the estimated cost of the work is \$50k or more), Quote Number, and the Quote Name. Quotes submitted without this information may be deemed non-responsive.

PROCUREMENT DEPARTMENT  
P.O. BOX 628 | COVINGTON, LOUISIANA | 70434 | [PROCUREMENT@STPGOV.ORG](mailto:PROCUREMENT@STPGOV.ORG) | 985-898-2520

[WWW.STPGOV.ORG](http://WWW.STPGOV.ORG)

Version 2022 Q1

Quotes will be received by the St. Tammany Parish Government Department of Procurement, located at 21454 Koop Dr., Suite 2F, Mandeville LA. 70471. The Procurement Department can be contacted by telephone at (985) 898-2520, or via e-mail at [Purchasing@stpgov.org](mailto:Purchasing@stpgov.org). St. Tammany Parish Government reserves the right to reject any or all quotes and to waive informalities.

Procurement Department

Name: 237 Blue Crane No. 1 Drive Drainage Repair

**Remove/ Replace drain pipe and Driveway**

Item	Description	Length	Width	Quantity	Unit
	<p><b>General Notes:</b></p> <ol style="list-style-type: none"> <li>Contractor shall field verify all quantities and measurements.</li> <li>Contractor shall be responsible for locating and protecting all existing utilities.</li> <li>Two-way traffic shall be maintained at all times during construction. Contractor shall have flagmen on both ends of work zone. If Police details are used for traffic control this does not take the place of flag men.</li> <li><b>Construction work shall not begin until signs, barricades, project signs and other traffic devices have been erected and approved. Contractor shall maintain project and construction signs.</b></li> <li>All existing sanitary/storm sewer lines shall be tied-in at no direct pay.</li> <li>Asphalt and concrete driveway tie-ins shall be tied in to existing surface material if in good shape.</li> <li>At all intersecting asphalt roads, contractor shall mill 1½” deep and 8’ into intersecting road for a smooth and clean transition. See Detail attached with Bid Proposal.</li> <li>Any <b>additional work</b> performed by the contractor <b>without prior written approval</b> from St Tammany Parish Department of Engineering, the cost of the work will be borne by the contractor and will not be reimbursed by the Parish.</li> <li>Contractor shall ensure roadway and shoulders drain accordingly without any surface ponding or bird baths after rain events. Contractor shall be required to fix these deficiencies at no direct pay.</li> <li>Materials Testing: All required testing and reporting shall be the contractor’s responsibility at no direct pay. Sampling and Testing will be performed in accordance with the St. Tammany Parish Roadway Testing and Inspection Standards for Residential Subdivisions (Attached with Bid Proposal) and LADOTD Standard Specifications for Roads and Bridges, Latest Edition 2016, Section 101 and 106.</li> <li>Roads and surrounding areas shall be dressed after 3 calendar days and no later than 10 calendar days of final asphalt wearing course. Late Fee of \$1.00 per Linear Foot per Calendar Day shall be charged if not completed with the specified time frame.</li> <li>If deep patching is required, the contractor is to compact at a minimum two equal lifts unless otherwise authorized.</li> <li>The existing asphalt has been cored by STP personnel to determine thickness and whether or not soil cement has been detected. Unless otherwise noted in the plans, the existing asphalt shall be reclaimed into the soil. If the contractor so chooses to mill the existing asphalt he may do so at no direct pay and retain 100% of the RAP. A separate sheet will be included with the bid tab to show existing thicknesses and base materials.</li> <li>If for any reason incidental construction occurs after the wearing course has been paved, the street MUST be protected from any scarring, gouging, scraping, ETC. If any of these occur the contractor shall be required to satisfactorily repair the deficiencies and/or be penalized a percentage of payment.</li> <li>The contractor MUST take care not to leave any asphalt “pattys” on the new OR existing street surface. The contractor WILL be required to remove them before it is considered complete.</li> </ol>				
	<p><b>Project Summary:</b> All labor, materials, equipment and supervision necessary to remove/replace side drain pipe and remove/replace concrete driveway.</p>				
727-01	<p><b>Mobilization:</b> All labor and materials necessary to accomplish preparatory work and operations, including those necessary for movement of personnel, equipment, supplies and incidentals to the project site.</p>			1	Lump Sum

All Work Shall Conform to Louisiana Standard Specifications for Roads and Bridges, Latest Edition 2016

**Remove/ Replace drain pipe and Driveway**

Item	Description	Length	Width	Quantity	Unit
701-06-01020	<b>Side Drain Pipe Arch (18" Equiv. RCPA):</b> All labor, materials and equipment necessary to remove/replace 18" Equivalent RCPA. Item shall include all required saw-cutting, excavation, backfill material and embankment. Item shall include removal and replacement of all unsuitable material as identified by St. Tammany Parish Engineering Department personnel. All pipe joints shall be wrapped with suitable geotextile fabric. Contractor installed pipe shall be cleaned of all debris and other materials prior to final acceptance. Side drain pipe installation shall be in accordance with Section 701 of LADOTD Standard Specifications, Latest Edition 2016.			40	Linear Foot
S-001	<b>Catch Basin Repair/Reseal:</b> All labor, materials, equipment and supervision necessary to remove the south wall of the existing catch basin, install the new 18" RCPA into the catch basin, and replace the wall with new concrete. Item shall include all saw-cutting and equipment necessary to remove /replace the wall. Contractor shall seal around the new pipe inside and out once the wall is replaced with non-shrink grout. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 702, Latest Edition 2016			1	Each
S-002	<b>Remove/Replace Concrete Driveway (6" Thick):</b> All labor, materials, equipment and supervision necessary to, in accordance with these specifications, Remove/Replace Concrete Driveway in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 706 and Section 202.02, Latest Edition 2016. Contractor shall be responsible for removal of all unsuitable base materials to a depth of 12" below the bottom grade of the new 6" thick concrete panel. Replacement material shall be river or pumped sand. Base repair and/or patch is not limited to a square yardage quantity, but may include the entire panel if directed by Engineering inspection staff. Concrete will be 4000# with micro fibers. Any damage caused by contractor operations shall be repaired immediately at no direct pay.			26	Square Yard
714-01-00700	<b>Sodding:</b> All labor, materials, equipment, and supervision to install slab sodding to disturbed or new areas. Plant, roll, and water the sod where needed. Water sod until rooted. Sod must be delivered and laid green free from brown spots.			1	Lump Sum

All Work Shall Conform to Louisiana Standard Specifications for Roads and Bridges, Latest Edition 2016